



Monday - Friday
8:00 AM - 4:30 PM

Tel: (413) 263-3242
Fax: (413) 734-9745

TOWN OF WEST SPRINGFIELD

DEPARTMENT OF PUBLIC WORKS

26 CENTRAL STREET

SUITE 17

WEST SPRINGFIELD, MA 01089-2763

WINTER SPECIFICATIONS

Work that is performed within the municipal right-of-way during the period November 30 thru April 1 must comply with the following:

- **If readily available, hot mix asphalt must be used for all roadway and sidewalk patches. If hot mix asphalt is not available, then a high performance cold patch equivalent to EZ Street Cold Mix or QPR (Quality Pavement Repair) must be used. If cold mix is used for restoration then the roadway patch must be replaced in accordance with our “Policy For Roadway Trench And Pavement Restoration” and the sidewalk must be restored to MassDOT specifications no later than June 1.**
- **The depth of temporary roadway or sidewalk patches made with high performance cold patch must match the existing depth of asphalt / concrete but not less than four (4) inches.**
- **If work is performed in the treebelt area, then it must be stabilized and made safe for the winter. This includes sidewalks. The impacted area will need to be completely restored in the Spring but no later than June 1.**
- **Contractors must address maintenance of job sites within 24 hours of being notified by the Department of Public Works.**